



RESTORING HISTORIC ALLIGATOR CREEK BRIDGE WITH INNOVATIVE GEOGRID

PRODUCTS USED

Triaxial Geogrid

- A multi-axial geogrid made from punched polypropylene sheets, forming a unique hexagonal structure with triangular apertures that confine and interlock with aggregate for soil stabilisation and ground improvement
- Reduces aggregate layer thickness by up to 50% without compromising performance, lowering excavation and fill costs
- Enhances layer stiffness to allow the use of lower-quality or recycled fill materials, reducing material costs
- Speeds up installation, offering a fast, cost-effective stabilisation solution for roads, working platforms and heavy-vehicle pavements

Similar Product

Geofabrics® Geogrid™ Triaxial

Bidim® Green Non-Woven Geotextile

- A strong three-dimensional structure with high elongation and equal biaxial strength properties in both directions
- Made with a combination of recycled PET and virgin plastic materials
- Provides excellent filtration, separation, drainage and protection performance
- Reduced need for quarried fill materials and reduced construction times

PROJECT DESCRIPTION

This project involved upgrading the historic Alligator Creek Bridge, located in Queensland. Originally built in 1911, the 253-metre-long bridge required maintenance as part of Queensland Rail's asset renewal program. The upgrades included the replacement of several ageing concrete piers and general maintenance to ensure the bridge's long-term structural integrity.

Geofabrics was approached by the lead contractor for suggestions to optimise the thickness of the working platform required for a tracked piling rig.

OUR SOLUTION

Geofabrics worked closely with the client's geotechnical engineer to propose a working platform using triaxial geogrids with a thickness of 300 millimetre. This reduced the working platform thickness by 45% compared to the alternative without geogrid. The platform thickness was determined using an approach that accurately assesses the positive effect of stabilising geogrids on the bearing capacity of working platforms, validated through full-scale testing.

The geogrid was laminated with Bidim Green A29G geotextile and placed in accordance with the installation guidelines provided by the manufacturer. A material specified by TMR Type 2.3 standards was used to construct the platform, with a total 1,150 square metres of triaxial geogrid procured for the project.

The client expressed satisfaction with both the installation of the geogrid solution and the overall outcome of the project. The client's representative commented, "The geosynthetic used not only allowed us to meet the desired loading capacity requirements on the piling pads but also enabled us to minimise the thickness required as intended. We look forward to more successful collaborations in the future".



45%
thinner platform

1,150 m²
total area covered



ABID ALI
SENIOR APPLICATIONS ENGINEER
GEOTECHNICS

☎ 0428 079 821

✉ A.ALI@GEOFABRICS.COM.AU

📍 GEOFABRICS CENTRE FOR GEOSYNTHETIC
RESEARCH, (GRID), GOLD COAST, QLD



Visit **geofabrics.co** or call 1300 60 60 20 (AU)
or **geofabrics.co.nz** or call 0800 60 60 20 (NZ)

GEOFABRICS®
Sustainable solutions

IMPORTANT NOTICE - DISCLAIMER - The images depicted in the photographs on this page are similar to the Geofabrics' products listed but they are not the same. The information contained in this brochure is general in nature. In particular the content of this brochure does not take account of specific conditions that may be present at your site. For full disclaimer and further information regarding installation visit geofabrics.co/disclaimer
© Copyright held by Geofabrics Australasia Pty Ltd. All rights are reserved and no part of this publication may be copied without prior permission. Published December 2025.

